

PROPOSAL PRICE SHEET (revised 05/30/18)

DEER MEADOW POSSUM CREEK CONNECTOR

CONTRACTOR:

Item No.	ODOT Item No.	Description	Estimated Quantity (A)	Unit	Unit Cost (B)	Total Item Cost A x B
BASE BID						
		ROADWAY				
1	201	CLEARING AND GRUBBING	1	LS		
2	202	PAVEMENT REMOVED	153	SY		
3	202	PIPE REMOVED	85	FT		
4	202	CATCH BASIN REMOVED	1	EACH		
5	SPECIAL	PIPE CLEANOUT, 24" AND UNDER	125	FT		
6	202	FENCE REMOVED	223	FT		
7	202	REMOVAL MISC.:WOOD POST REMOVED	1	EACH		
8	203	EXCAVATION	1,215	CY		
9	203	EMBANKMENT	446	CY		
10	204	SUBGRADE COMPACTION	5,685	SY		
11	204	PROOF ROLLING	2	HOUR		
12	607	FENCE, MISC.: BIKEWAY RAILING	80	FT		
13	608	DETECTABLE WARNING	139	SF		
		EROSION CONTROL				
14	601	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	52	CY		
15	616	WATER	5	MGAL		
16	659	TOPSOIL	263	CY		
17	659	SEEDING AND MULCHING, CLASS 2	10,479	SY		
18	659	COMMERCIAL FERTILIZER	1.40	TON		
19	659	WATER	57	MGAL		
20	670	SLOPE EROSION PROTECTION	2,360	SY		
21	832	STORM WATER POLLUTION PREVENTION PLAN	1	LS		
22	832	EROSION CONTROL	54,000	EACH	\$ 1.00	\$ 54,000.00
		DRAINAGE				
23	602	CONCRETE MASONRY	2.2	CY		
24	611	6" CONDUIT, TYPE E	10	FT		
25	611	6" CONDUIT, TYPE F	10	FT		
26	611	8" CONDUIT, TYPE B	20	FT		

DEER MEADOW POSSUM CREEK CONNECTOR

CONTRACTOR:

Item No.	ODOT Item No.	Description	Estimated Quantity (A)	Unit	Unit Cost (B)	Total Item Cost A x B
27	611	8" CONDUIT, TYPE D, ADS N-12 OR APPROVED EQUAL	21	FT		
28	611	12" CONDUIT, TYPE B	42	FT		
29	611	12" CONDUIT, TYPE D	127	FT		
30	611	15" CONDUIT, TYPE B	62	FT		
31	611	30" CONDUIT, TYPE D	50	FT		
32	611	34" X 53" CONDUIT, TYPE D, 706.04	60	FT		
33	611	CATCH BASIN, NO. 5	2	EACH		
		PAVEMENT				
34	301	ASPHALT CONCRETE BASE, PG64-22	10	CY		
35	304	AGGREGATE BASE	802	CY		
36	407	TACK COAT	284	GAL		
37	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	145	CY		
38	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	244	CY		
		WATER WORK				
39	638	VALVE BOX ADJUSTED TO GRADE	1	EACH		
		TRAFFIC CONTROL				
40	630	GROUND MOUNTED SUPPORT, NO. 3 POST	468	FT		
41	630	SIGN, FLAT SHEET	163.5	SF		
42	630	SIGNING, MISC.: SOLAR POWERED & WIRELESS RECTANGULAR RAPID FLASHING BEACONS (RRFB) SIGNAL ON BREAKAWAY PEDESTAL	1	EACH		
43	642	STOP LINE	59	FT		
44	642	CROSSWALK LINE	84	FT		
45	642	SHARED MARKING, TYPE 1	64	EACH		
46	642	REMOVAL OF PAVEMENT MARKING	20	FT		
		MAINTENANCE OF TRAFFIC				
47	410	TRAFFIC COMPACTED SURFACE, TYPE A OR B	20	CY		
48	410	TRAFFIC COMPACTED SURFACE, TYPE C	20	CY		
49	614	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	10	CY		
50	616	WATER	5	MGAL		
		INCIDENTALS				
51	614	MAINTAINING TRAFFIC	1	LS		
52	623	CONSTRUCTION LAYOUT STAKES AND SURVEYING	1	LS		

DEER MEADOW POSSUM CREEK CONNECTOR

CONTRACTOR:

Item No.	ODOT Item No.	Description	Estimated Quantity (A)	Unit	Unit Cost (B)	Total Item Cost A x B
53	624	MOBILIZATION	1	LS		

Grand Total Base Bid Cost \$

PAVEMENT ALTERNATES*

37A	SPECIAL	THINLAY ASPHALT CONCRETE (ALTERNATE)	140	CY		
-----	---------	--------------------------------------	-----	----	--	--

ADD ALTERNATE I - RESURFACE PATH FROM DEER MEADOW PARK TO MAIN STREET**

54	407	TACK COAT	210	GAL		
55	441	1" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	65	CY		
55A	SPECIAL	THINLAY ASPHALT CONCRETE (ALTERNATE)	65	CY		

Grand Total Add Alternate I Bid Cost \$**

ADD ALTERNATE II* - RESURFACE LOOP AROUND DEER MEADOW PARK POND**

56	407	TACK COAT	220	GAL		
57	441	1" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	70	CY		
57A	SPECIAL	1" THINLAY ASPHALT CONCRETE (ALTERNATE)	70	CY		

Grand Total Add Alternate II Bid Cost* \$**

* PAVEMENT ALTERNATES BID ITEM, IF ACCEPTED, WILL REPLACE A CORRESPONDING AMOUNT OF SURFACE COURSE IN THE BASE B

** INCLUDE ITEM 54 AND THE LESSER OF ITEMS 55/55A IN THE GRAND TOTAL. OWNER RESERVES THE RIGHT TO ACCEPT EITHER ITEM.

*** INCLUDE ITEM 56 AND THE LESSER OF ITEMS 57/57A IN THE GRAND TOTAL. OWNER RESERVES THE RIGHT TO ACCEPT EITHER ITEM.

NOTE: OWNER RESERVES THE RIGHT TO ACCEPT OR REJECT ANY OR ALL ALTERNATES